



SPLASHLIGHT-24VDC NOZZLE ASSEMBLY WITH LED LIGHT





HYDRAULIC DATA											
NOZZLE COVER		SPRAY HEIGHT									
		2'-0"	4'-0"	6'-0"	8'-0"	10'-0"	12'-0"				
JC SJ AJ TT	GPM	8.6	11.7	14.0	15.7	18.2	19.6				
	HEAD	29.0'	38.0'	52.2'	54.0'	65.0'	56.0'				
APJ-50	GPM	8.0	10.5	12.5	14.5	16.5	18.0				
	HEAD	28.0'	34.0'	41.0'	49.0'	58.0'	48.0'				

ELEVATION

HYDRAULIC DATA										
NOZZLE COVER		SPRAY HEIGHT								
		2'-0"	4'-0"	6'-0"	8'-0"	10'-0"	12'-0"	14'-0"		
JC/L	GPM	7.2	9.5	11.6	13.3	15.0	16.5	17.9		
	HEAD	24.0'	30.0'	37.0'	43.0'	49.0'	55.0'	62.0'		
APJ-38	GPM	7.0	9.5	12.0	13.5	15.5	16.5	18.0		
	HEAD	28.5'	34.0'	39.0'	44.0'	49.0'	54.0'	60.0'		

IF EXCESSIVE DEBRIS PRESENT

SPECIFICATION DATA: Flush-mounted Nozzle/LED Assembly, consisting of high strength polypro niche with integral water-stop key flange, threaded inserts to accept eyebolts and jamb-nuts (included for installation), Stainless Steel grate, fast-acting waterswitch and RDHN-Series, S.S. Nozzle Body with choice of nozzle cover; see catalog sheet 1.716 for available nozzle spray patterns; use tables above for Hydraulic Data.

<u>DESIGN APPLICATION DATA</u>: 3" (F) N.P.T. drain return connection, 1-1/2" (F) N.P.T. supply connection, two (2) 3/4" (F) N.P.T. conduit connections (one for LED light fixture and one for nozzle/valve assembly), one high-output RFL-DH-24VDC SERIES (White or RGBW), LED light fixture with pre-attached 25' cord recessed into the nozzle body and one manual brass balancing valve.

NOTES: 1. Installer must provide 1/2" threaded rod, flat washers and nuts at four support points for poly niche installation.

3" (F) N.P.T. GRAVITY DRAIN

RETURN CONNECTION

- 2. Fine Screening at pump is recommended (500 microns).
- 3. 24 VDC power supply required to operate light fixtures. Contact factory for requirements.
- 4. DMX driver required to operate 'RGB' light fixtures in programmable mode; contact factory for requirements.
- 5. Sequencing Controller and 24VDC Power Supply required for 24 VDC 'on/off' nozzle triggering; contact factory for requirements.
- 6. Due to continuing product improvement program, Roman Fountains reserves the right to change the specifications without notice.

1.404a /